

PROJECT	MACDILL AIR FORCE BASE						
ADDRESS	TAMPA, FLORIDA						
							
DESCRIPTION			TOTAL HOURS	LABOR INCL. O&P	MATERIAL INCL O&P	SUBTOTAL INCL O&P	
BASE BID							
	BUILDING CONCRETE HANGER 1		12600 HRS	\$ 1,507,220	\$ 1,619,888	\$	3,127,108
	BUILDING CONCRETE HANGER 4		12551 HRS	\$ 1,481,838	\$ 1,622,109	\$	3,103,947
	BUILDING CONCRETE HANGER 5		11691 HRS	\$ 1,378,462	\$ 1,471,423	\$	2,849,885
	Subtotal		36842 HRS	\$ 4,367,520	\$ 4,713,420	\$	9,080,940
	Sales Tax	6.63%			\$ 260,220	\$	260,220
TOTAL BASE BID (INCL. OVERHEAD AND PROFIT)				\$ 4,367,520	\$ 4,973,640	\$	9,341,160
TOTAL HRS (ASSUMED 3 LABORS CREW)			36842 HRS				
TOTAL LABOR COST INCL O&P			\$	4,367,520			
TOTAL MATERIAL COST INCL O,P&TAX			\$	4,973,640			

See next tab for detailed take-offs.

PROJECT				MACDILL AIR FORCE BASE				Email support@aconengineering.com				Pricing cells				O&P 20.00% 							
ADDRESS				TAMPA, FLORIDA				PH #				Confirm pricing											
DUE DATE				10/28/2025				Website http://aconengineering.com/				Please Add/Confirm Price											
DATE ON PLANS				8/18/2025				Concrete (5000 PSI)				1737 CY											
ADDENDUM UPDATE				Not Issued				Rebars				170 TONS											
								6x6xW2.0xW2.0 WWF				SF											
Total Base bid				\$3,216,539				CONCRETE HANGER 1															
SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	LABOR/ EQUIP. COST	MATERIAL COST	SUBCONT. COST	UNIT MANHOURS	HOURLY WAGE	TOTAL HOURS	TOTAL LABOR	TOTAL MATERIAL COST	TOTAL SUB CONTRACTOR	TOTAL UNIT COST	TOTAL COST	SUBTOTALS			
BUILDING CONCRETE																							
				LAYOUT																			
1				Layout & Job planning	1	0%	1	LS	\$ 185,000.00	\$ -	\$ -	0.00 HRS	\$ -	0.00 HRS	\$ 222,000.00	\$ -	\$ -	\$ 222,000.00	\$ 222,000				
				Sub Total											\$ 222,000	\$ -	\$ -			\$ 222,000			
				FOUNDATION PLAN																			
				PAD FOOTINGS																			
2	S101	J12/S533		Concrete (5000 Psi)	1	10%	1	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	2.25 HRS	\$ 229.24	\$ 388.24	\$ -	\$ 505.21	\$ 617				
3	S101	J12/S533		Reinforcement	215	10%	237	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	4.04 HRS	\$ 412.20	\$ 702.16	\$ -	\$ 4.70	\$ 1,114				
4	S101	J12/S533		Formwork, Pad footings	27	10%	30	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	2.89 HRS	\$ 294.39	\$ -	\$ -	\$ 9.91	\$ 294				
5	S101	J12/S533		Excavation	3	10%	4	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	2.21 HRS	\$ 225.28	\$ -	\$ -	\$ 61.44	\$ 225				
6	S101	J12/S533		Backfill	2	10%	2	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	1.25 HRS	\$ 127.86	\$ -	\$ -	\$ 52.31	\$ 128				
				Please see next tab for detailed calculations																			
				Sub Total											\$ 1,289	\$ 1,090	\$ -			\$ 2,379			
				PILE CAPS																			
7	S105	K4/S531		Concrete (5000 Psi)	885	10%	973	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	1790.06 HRS	\$ 182,586.60	\$ 309,229.05	\$ -	\$ 505.21	\$ 491,816				
8	S105	K4/S531		Reinforcement	180069	10%	198,076	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	3378.94 HRS	\$ 344,652.35	\$ 587,097.46	\$ -	\$ 4.70	\$ 931,750				
9	S105	K4/S531		Formwork, Pile Caps	3575	10%	3,933	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	382.17 HRS	\$ 38,981.01	\$ -	\$ -	\$ 9.91	\$ 38,981				
10	S105	K4/S531		Excavation	1378	10%	1,516	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	913.18 HRS	\$ 93,143.89	\$ -	\$ -	\$ 61.44	\$ 93,144				
11	S105	K4/S531		Backfill	507	10%	558	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	286.17 HRS	\$ 29,189.01	\$ -	\$ -	\$ 52.31	\$ 29,189				
				THICKENED EDGE L=25'-4" W=3'-6" D=2'																			
12	S105	K4/S531		Concrete (5000 Psi)	7	10%	7	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	13.30 HRS	\$ 1,356.49	\$ 2,297.35	\$ -	\$ 505.21	\$ 3,654				
13	S105	K4/S531		(9) #5 Cont. Bar	276	10%	304	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.18 HRS	\$ 528.54	\$ 900.34	\$ -	\$ 4.70	\$ 1,429				
14	S105	K4/S531		#5 @ 12" O.C Dowel	295	10%	325	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.54 HRS	\$ 564.64	\$ 961.83	\$ -	\$ 4.70	\$ 1,526				
				Please see next tab for detailed calculations																			
				Sub Total											\$ 691,003	\$ 900,486	\$ -			\$ 1,591,489			
				TIE BEAMS																			
15	S101	A1/S523		Concrete (5000 Psi)	116	10%	127	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	233.91 HRS	\$ 23,859.26	\$ 40,408.10	\$ -	\$ 505.21	\$ 64,267				
16	S101	A1/S523		Reinforcement (Tension Ties)	27817	10%	30,599	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	521.98 HRS	\$ 53,241.49	\$ 90,694.12	\$ -	\$ 4.70	\$ 143,936				
17	S101	A1/S523		Reinforcement	5595	10%	6,155	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	105.00 HRS	\$ 10,709.70	\$ 18,243.42	\$ -	\$ 4.70	\$ 28,953				
18	S101	A1/S523		Formwork Beams	1702	10%	1,872	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	181.89 HRS	\$ 18,552.64	\$ -	\$ -	\$ 9.91	\$ 18,553				
19	S101	A1/S523		Excavation	167	10%	183	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	110.36 HRS	\$ 11,257.02	\$ -	\$ -	\$ 61.44	\$ 11,257				
20	S101	A1/S523		Backfill	133	10%	146	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	74.76 HRS	\$ 7,625.63	\$ -	\$ -	\$ 52.31	\$ 7,626				
				Please see next tab for detailed calculations																			
				Sub Total											\$ 125,246	\$ 149,346	\$ -			\$ 274,591			
				CONCRETE WALLS																			
21	S101	A12/S533		Concrete (5000 Psi)	19	10%	20	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	37.64 HRS	\$ 3,839.77	\$ 6,503.04	\$ -	\$ 505.21	\$ 10,343				
22	S101	A12/S533		Reinforcement	5055	10%	5,560	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	94.85 HRS	\$ 9,674.69	\$ 16,480.34	\$ -	\$ 4.70	\$ 26,155				
23	S101	A12/S533		Formwork Walls	1005	10%	1,106	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	107.43 HRS	\$ 10,957.72	\$ -	\$ -	\$ 9.91	\$ 10,958				
				Please see next tab for detailed calculations																			
				Sub Total											\$ 24,472	\$ 22,983	\$ -			\$ 47,456			
				CONCRETE PADESTALS																			
24	S101	J12/S533		Concrete (5000 Psi)	1	10%	0.9	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	1.63 HRS	\$ 165.82	\$ 280.83	\$ -	\$ 505.21	\$ 447				
25	S101	J12/S533		Reinforcement	275	10%	303	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.16 HRS	\$ 526.77	\$ 897.32	\$ -	\$ 4.70	\$ 1,424				
26	S101	J12/S533		Formwork Pedestal	30	10%	33	SFCA	\$ 8	\$ -	\$ -	0.10 HRS	\$ 85	3.25 HRS	\$ 331.24	\$ -	\$ -	\$ 9.91	\$ 331				
				Please see next tab for detailed calculations																			
				Sub-Total											\$ 1,024	\$ 1,178	\$ -			\$ 2,202			
				FOUNDATION PLAN																			
				SLABS ON GRADE																			
				8" SLAB ON GRADE																			
27	S115	Plan	28 CY	8" Slab W/ #6 @ 12" O.C EW Bars	1035	10%	1,138	SF	\$ 4.16	\$ 7.29	\$ -	0.05 HRS	\$ 85	55.71 HRS	\$ 5,682.62	\$ 9,958.25	\$ -	\$ 13.74	\$ 15,641				
28	S115	Plan		#6 @ 12" O.C EW Bars	3702	10%	4,072	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	69.46 HRS	\$ 7,085.32	\$ 12,069.48	\$ -	\$ 4.70	\$ 19,155				
29	S115	Plan		Vapor Barrier	1035	10%	1,138	SF	\$ 0.67	\$ 0.77	\$ -	0.01 HRS	\$ 85	8.97 HRS	\$ 915.23	\$ 1,051.83	\$ -	\$ 1.73	\$ 1,967				
30	S115	Plan		Compacted Fill	1035	10%	1,138	SF	\$ 0.75	\$ -	\$ -	0.01 HRS	\$ 85	10.04 HRS	\$ 1,024.51	\$ -	\$ -	\$ 0.90	\$ 1,025				

SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	LABOR/ EQUIP. COST	MATERIAL COST	SUBCONT. COST	UNIT MANHOURS	HOURLY WAGE	TOTAL HOURS	TOTAL LABOR	TOTAL MATERIAL COST	TOTAL SUB CONTRACTOR	TOTAL UNIT COST	TOTAL COST	SUBTOTALS
31	S115	Plan		Sawcut Control Joint	166	10%	182	LF	\$ 1.40	\$ -	\$ -	0.02 HRS	\$ 85	3.00 HRS	\$ 305.99	\$ -	\$ -	\$ 1.68	\$ 306	
32	S115	Plan		Expansion Joint	83	10%	91	LF	\$ 1.16	\$ 1.42	\$ -	0.01 HRS	\$ 85	1.24 HRS	\$ 126.77	\$ 155.18	\$ -	\$ 3.10	\$ 282	
33	S115	Plan		8" Edge Form	306	10%	337	LF	\$ 6.85	\$ 2.73	\$ -	0.08 HRS	\$ 85	27.13 HRS	\$ 2,766.85	\$ 1,102.70	\$ -	\$ 11.50	\$ 3,870	
				8" SLAB ON GRADE																
34	S115	Plan	179 CY	8" Slab W/ #6 @ 12" O.C EW Bars	6599	10%	7,259	SF	\$ 4.16	\$ 7.29	\$ -	0.05 HRS	\$ 85	355.28 HRS	\$ 36,238.35	\$ 63,504.23	\$ -	\$ 13.74	\$ 99,743	
35	S115	Plan		#6 @ 12" O.C EW Bars	23607	10%	25,967	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	442.97 HRS	\$ 45,183.41	\$ 76,967.61	\$ -	\$ 4.70	\$ 122,151	
36	S115	Plan		Vapor Barrier	6599	10%	7,259	SF	\$ 0.67	\$ 0.77	\$ -	0.01 HRS	\$ 85	57.22 HRS	\$ 5,836.47	\$ 6,707.58	\$ -	\$ 1.73	\$ 12,544	
37	S115	Plan		Compacted Fill	6599	10%	7,259	SF	\$ 0.75	\$ -	\$ -	0.01 HRS	\$ 85	64.05 HRS	\$ 6,533.36	\$ -	\$ -	\$ 0.90	\$ 6,533	
38	S115	Plan		Sawcut Control Joint	1056	10%	1,161	LF	\$ 1.40	\$ -	\$ -	0.02 HRS	\$ 85	19.13 HRS	\$ 1,951.30	\$ -	\$ -	\$ 1.68	\$ 1,951	
39	S115	Plan		Expansion Joint	528	10%	581	LF	\$ 1.16	\$ 1.42	\$ -	0.01 HRS	\$ 85	7.93 HRS	\$ 808.39	\$ 989.59	\$ -	\$ 3.10	\$ 1,798	
40	S115	Plan		8" Edge Form	490	10%	539	LF	\$ 6.85	\$ 2.73	\$ -	0.08 HRS	\$ 85	43.44 HRS	\$ 4,430.58	\$ 1,765.76	\$ -	\$ 11.50	\$ 6,196	
				12.5" SLAB ON GRADE																
41	S115	Plan	255 CY	12.5" Concrete Slab at Keel section W/ #6 @ 12" O.C EW T&B Bars	6020	10%	6,622	SF	\$ 5.94	\$ 10.26	\$ -	0.07 HRS	\$ 85	462.74 HRS	\$ 47,199.34	\$ 81,526.14	\$ -	\$ 19.44	\$ 128,725	
42	S115	Plan		#6 @ 12" O.C EW T&B Bars	43067	10%	47,373	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	808.13 HRS	\$ 82,429.65	\$ 140,414.64	\$ -	\$ 4.70	\$ 222,844	
43	S115	Plan		Vapor Barrier	6020	10%	6,622	SF	\$ 0.67	\$ 0.77	\$ -	0.01 HRS	\$ 85	52.19 HRS	\$ 5,323.83	\$ 6,118.43	\$ -	\$ 1.73	\$ 11,442	
44	S115	Plan		Compacted Fill	6020	10%	6,622	SF	\$ 0.75	\$ -	\$ -	0.01 HRS	\$ 85	58.43 HRS	\$ 5,959.51	\$ -	\$ -	\$ 0.90	\$ 5,960	
45	S115	Plan		Sawcut Control Joint	963	10%	1,059	LF	\$ 1.40	\$ -	\$ -	0.02 HRS	\$ 85	17.45 HRS	\$ 1,779.91	\$ -	\$ -	\$ 1.68	\$ 1,780	
46	S115	Plan		Expansion Joint	482	10%	530	LF	\$ 1.16	\$ 1.42	\$ -	0.01 HRS	\$ 85	7.23 HRS	\$ 737.39	\$ 902.67	\$ -	\$ 3.10	\$ 1,640	
47	S115	Plan		8" Edge Form	490	10%	539	LF	\$ 6.85	\$ 2.73	\$ -	0.08 HRS	\$ 85	43.44 HRS	\$ 4,430.58	\$ 1,765.76	\$ -	\$ 11.50	\$ 6,196	
48	S115	Plan		Formwork	719	10%	791	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	76.83 HRS	\$ 7,836.68	\$ -	\$ -	\$ 9.91	\$ 7,837	
				Sub Total											\$ 274,586	\$ 405,000	\$ -			\$ 679,586
				EQUIPMENT PADS																
				24" THICK EQUIPMENT PAD																
49	S103	Plan	14 CY	24" Thick Equipment Pad W/ #7 @ 10" O.C EW T&B Bars	167	10%	184	SF	\$ 9.20	\$ 22.94	\$ -	0.11 HRS	\$ 85	19.86 HRS	\$ 2,026.10	\$ 5,052.05	\$ -	\$ 38.57	\$ 7,078	
50	S103	Plan		#7 @ 10" O.C EW T&B Bars	1664	10%	1,831	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	31.23 HRS	\$ 3,185.24	\$ 5,425.90	\$ -	\$ 4.70	\$ 8,611	
51	S103	Plan		Formwork	110	10%	121	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	11.76 HRS	\$ 1,199.35	\$ -	\$ -	\$ 9.91	\$ 1,199	
				6" THICK EQUIPMENT PAD																
52	S103	Plan	8 CY	6" Concrete Pad @ Mechanical Area	416	10%	457	SF	\$ 3.20	\$ 5.63	\$ -	0.04 HRS	\$ 85	17.21 HRS	\$ 1,755.87	\$ 3,089.24	\$ -	\$ 10.60	\$ 4,845	
53	S103	Plan		#6 @ 12" O.C EW Bars	1487	10%	1,636	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	27.90 HRS	\$ 2,846.08	\$ 4,848.15	\$ -	\$ 4.70	\$ 7,694	
54	S103	Plan		6" Edge Form	117	10%	129	LF	\$ 5.24	\$ 1.64	\$ -	0.06 HRS	\$ 85	7.93 HRS	\$ 809.27	\$ 253.28	\$ -	\$ 8.26	\$ 1,063	
				Sub Total											\$ 11,822	\$ 18,669	\$ -			\$ 30,491
				CONCRETE CURBS																
				CONCRETE CURB L=501' W=0'-8" D=0'-5"																
55	S112	F1/S555		Concrete (5000 Psi)	5	10%	6	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	10.56 HRS	\$ 1,077.41	\$ 1,824.71	\$ -	\$ 505.21	\$ 2,902	
56	S112	F1/S555		(2) #5 Cont. Bar	1212	10%	1,334	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	22.75 HRS	\$ 2,320.62	\$ 3,953.06	\$ -	\$ 4.70	\$ 6,274	
57	S112	F1/S555		#5 @ 12" O.C Dowel	1215	10%	1,336	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	22.80 HRS	\$ 2,325.25	\$ 3,960.94	\$ -	\$ 4.70	\$ 6,286	
				CONCRETE CURB L=240' W=0'-10" D=1'-0"																
58	S112	G8/S522		Concrete (5000 Psi)	7	10%	8	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	14.92 HRS	\$ 1,522.15	\$ 2,577.92	\$ -	\$ 505.21	\$ 4,100	
59	S112	G8/S522		(2) #6 Cont. Bar	859	10%	945	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	16.12 HRS	\$ 1,643.81	\$ 2,800.15	\$ -	\$ 4.70	\$ 4,444	
60	S112	G8/S522		#4 @ 12" O.C Dowel	1578	10%	1,736	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	29.61 HRS	\$ 3,019.92	\$ 5,144.27	\$ -	\$ 4.70	\$ 8,164	
				Sub Total											\$ 11,909	\$ 20,261	\$ -			\$ 32,170
				LEVEL 2																
				COMPOSITE DECK																
				3.75" CONCRETE SLAB OVER 1.5" METAL DECK																
61	S121	Plan	108 CY	3.75" Concrete over 1.5" Metal Deck W/ #4 @ 12" O.C EW Bars	7043	10%	7,747	SF	\$ 1.98	\$ 3.34	\$ -	0.02 HRS	\$ 85	180.46 HRS	\$ 18,406.83	\$ 31,049.90	\$ -	\$ 6.38	\$ 49,457	
62	S121	Plan		#4 @ 12" O.C EW Bars	10632	10%	11,695	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	199.51 HRS	\$ 20,350.10	\$ 34,665.35	\$ -	\$ 4.70	\$ 55,015	
63	S121	Plan		5" Pour Stop	690	10%	759	LF	\$ 2.10	\$ 3.82	\$ -	0.02 HRS	\$ 85	18.75 HRS	\$ 1,912.68	\$ 3,479.26	\$ -	\$ 7.10	\$ 5,392	
				Sub Total											\$ 40,670	\$ 69,195	\$ -			\$ 109,864
				MISC. INSTALLATION																
64				Misc. Coordinated Installations	1	0%	1	LS	\$ 11,000.00	\$ 26,400.00	\$ -	129.41 HRS	\$ 85	129.41 HRS	\$ 13,200.00	\$ 31,680.00	\$ -	\$ 44,880.00	\$ 44,880	
				Sub Total											\$ 13,200	\$ 31,680	\$ -			\$ 44,880
				SPOIL HAULAGE																

[illegible]

PROJECT ADDRESS DUE DATE DATE ON PLANS ADDENDUM UPDATE				MACDILL AIR FORCE BASE TAMPA, FLORIDA 10/28/2025 8/18/2025 Not Issued				Email support@aconengineering.com PH # Website http://aconengineering.com/ Concrete (5000 PSI) 1783 CY Rebars 170 TONS 6x6xW2.0xW2.0 WWF SF				Pricing cells Confirm pricing Please Add/Confirm Price				O&P 20.00%					
Total Base bid				\$3,193,501				CONCRETE HNAGER 4													
SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	LABOR/ EQUIP. COST	MATERIAL COST	SUBCONT. COST	UNIT MANHOURS	HOURLY WAGE	TOTAL HOURS	TOTAL LABOR	TOTAL MATERIAL COST	TOTAL SUB CONTRACTOR	TOTAL UNIT COST	TOTAL COST	SUBTOTALS	
BUILDING CONCRETE																					
				LAYOUT																	
1				Layout & Job planning	1	0%	1	LS	\$ 168,000.00	\$ -	\$ -	0.00 HRS	\$ -	0.00 HRS	\$ 201,600.00	\$ -	\$ -	\$ 201,600.00	\$ 201,600		
				Sub Total											\$ 201,600	\$ -	\$ -			\$ 201,600	
				FOUNDATION PLAN																	
				PAD FOOTINGS																	
2	S101	J12/S533		Concrete (5000 Psi)	1	10%	1	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	2.25 HRS	\$ 229.24	\$ 388.24	\$ -	\$ 505.21	\$ 617		
3	S101	J12/S533		Reinforcement	215	10%	237	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	4.04 HRS	\$ 412.20	\$ 702.16	\$ -	\$ 4.70	\$ 1,114		
4	S101	J12/S533		Formwork, Pad footings	27	10%	30	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	2.89 HRS	\$ 294.39	\$ -	\$ -	\$ 9.91	\$ 294		
5	S101	J12/S533		Excavation	3	10%	4	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	2.21 HRS	\$ 225.28	\$ -	\$ -	\$ 61.44	\$ 225		
6	S101	J12/S533		Backfill	2	10%	2	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	1.25 HRS	\$ 127.86	\$ -	\$ -	\$ 52.31	\$ 128		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 1,289	\$ 1,090	\$ -			\$ 2,379	
				PILE CAPS																	
7	S105	K4/S531		Concrete (5000 Psi)	890	10%	979	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	1799.80 HRS	\$ 183,579.67	\$ 310,910.91	\$ -	\$ 505.21	\$ 494,491		
8	S105	K4/S531		Reinforcement	180069	10%	198,076	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	3378.94 HRS	\$ 344,652.35	\$ 587,097.46	\$ -	\$ 4.70	\$ 931,750		
9	S105	K4/S531		Formwork, Pile Caps	3575	10%	3,933	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	382.17 HRS	\$ 38,981.01	\$ -	\$ -	\$ 9.91	\$ 38,981		
10	S105	K4/S531		Excavation	1387	10%	1,525	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	918.75 HRS	\$ 93,712.35	\$ -	\$ -	\$ 61.44	\$ 93,712		
11	S105	K4/S531		Backfill	510	10%	561	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	287.76 HRS	\$ 29,351.14	\$ -	\$ -	\$ 52.31	\$ 29,351		
				THICKENED EDGE L=25'-4" W=3'-6" D=2'																	
12	S105	K4/S531		Concrete (5000 Psi)	7	10%	7	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	13.30 HRS	\$ 1,356.49	\$ 2,297.35	\$ -	\$ 505.21	\$ 3,654		
13	S105	K4/S531		(9) #5 Cont. Bar	276	10%	304	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.18 HRS	\$ 528.54	\$ 900.34	\$ -	\$ 4.70	\$ 1,429		
14	S105	K4/S531		#5 @ 12" O.C Dowel	295	10%	325	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.54 HRS	\$ 564.64	\$ 961.83	\$ -	\$ 4.70	\$ 1,526		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 692,726	\$ 902,168	\$ -			\$ 1,594,894	
				TIE BEAMS																	
15	S101	A1/S523		Concrete (5000 Psi)	116	10%	127	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	233.83 HRS	\$ 23,851.06	\$ 40,394.20	\$ -	\$ 505.21	\$ 64,245		
16	S101	A1/S523		Reinforcement (Tension Ties)	27817	10%	30,599	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	521.98 HRS	\$ 53,241.49	\$ 90,694.12	\$ -	\$ 4.70	\$ 143,936		
17	S101	A1/S523		Reinforcement	5595	10%	6,155	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	105.00 HRS	\$ 10,709.70	\$ 18,243.42	\$ -	\$ 4.70	\$ 28,953		
18	S101	A1/S523		Formwork Beams	1701	10%	1,871	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	181.83 HRS	\$ 18,546.26	\$ -	\$ -	\$ 9.91	\$ 18,546		
19	S101	A1/S523		Excavation	167	10%	183	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	110.36 HRS	\$ 11,257.02	\$ -	\$ -	\$ 61.44	\$ 11,257		
20	S101	A1/S523		Backfill	133	10%	146	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	74.76 HRS	\$ 7,625.63	\$ -	\$ -	\$ 52.31	\$ 7,626		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 125,231	\$ 149,332	\$ -			\$ 274,563	
				CONCRETE WALLS																	
21	S101	A12/S533		Concrete (5000 Psi)	19	10%	21	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	37.78 HRS	\$ 3,853.52	\$ 6,526.34	\$ -	\$ 505.21	\$ 10,380		
22	S101	A12/S533		Reinforcement	5073	10%	5,580	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	95.19 HRS	\$ 9,709.20	\$ 16,539.12	\$ -	\$ 4.70	\$ 26,248		
23	S101	A12/S533		Formwork Walls	1009	10%	1,109	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	107.81 HRS	\$ 10,996.97	\$ -	\$ -	\$ 9.91	\$ 10,997		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 24,560	\$ 23,065	\$ -			\$ 47,625	
				CONCRETE PADESTALS																	
24	S101	J12/S533		Concrete (5000 Psi)	1	10%	0.9	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	1.63 HRS	\$ 165.82	\$ 280.83	\$ -	\$ 505.21	\$ 447		
25	S101	J12/S533		Reinforcement	275	10%	303	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.16 HRS	\$ 526.77	\$ 897.32	\$ -	\$ 4.70	\$ 1,424		
26	S101	J12/S533		Formwork Pedestal	30	10%	33	SFCA	\$ 8	\$ -	\$ -	0.10 HRS	\$ 85	3.25 HRS	\$ 331.24	\$ -	\$ -	\$ 9.91	\$ 331		
				Please see next tab for detailed calculations																	
				Sub-Total											\$ 1,024	\$ 1,178	\$ -			\$ 2,202	
				FOUNDATION PLAN																	
				SLABS ON GRADE																	
				8" SLAB ON GRADE																	
27	S115	Plan	5 CY	8" Slab W/ #6 @ 12" O.C EW Bars	188	10%	207	SF	\$ 4.16	\$ 7.29	\$ -	0.05 HRS	\$ 85	10.13 HRS	\$ 1,032.78	\$ 1,809.86	\$ -	\$ 13.74	\$ 2,843		
28	S115	Plan		#6 @ 12" O.C EW Bars	673	10%	740	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	12.62 HRS	\$ 1,287.72	\$ 2,193.56	\$ -	\$ 4.70	\$ 3,481		
29	S115	Plan		Vapor Barrier	188	10%	207	SF	\$ 0.67	\$ 0.77	\$ -	0.01 HRS	\$ 85	1.63 HRS	\$ 166.34	\$ 191.16	\$ -	\$ 1.73	\$ 358		
30	S115	Plan		Compacted Fill	188	10%	207	SF	\$ 0.75	\$ -	\$ -	0.01 HRS	\$ 85	1.83 HRS	\$ 186.20	\$ -	\$ -	\$ 0.90	\$ 186		

SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	LABOR/ EQUIP. COST	MATERIAL COST	SUBCONT. COST	UNIT MANHOURS	HOURLY WAGE	TOTAL HOURS	TOTAL LABOR	TOTAL MATERIAL COST	TOTAL SUB CONTRACTOR	TOTAL UNIT COST	TOTAL COST	SUBTOTALS
EXCLUSIONS Waterproofing Rigid Insulation Grounding Wire																				

PROJECT ADDRESS DUE DATE DATE ON PLANS ADDENDUM UPDATE				MACDILL AIR FORCE BASE TAMPA, FLORIDA 10/28/2025 8/18/2025 Not Issued				Email support@aconengineering.com PH # Website http://aconengineering.com/ Concrete (5000 PSI) 1557 CY Rebars 157 TONS 6x6xW2.0xW2.0 WWF SF				Pricing cells Confirm pricing Please Add/Confirm Price				O&P 20.00%					
Total Base bid				\$2,931,120				CONCRETE HANGER 5													
SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	LABOR/ EQUIP. COST	MATERIAL COST	SUBCONT. COST	UNIT MANHOUR S	HOURLY WAGE	TOTAL HOURS	TOTAL LABOR	TOTAL MATERIAL COST	TOTAL SUB CONTRACTO R	TOTAL UNIT COST	TOTAL COST	SUBTOTALS	
BUILDING CONCRETE																					
LAYOUT																					
1				Layout & Job planning	1	0%	1	LS	\$ 155,000.00	\$ -	\$ -	0.00 HRS	\$ -	0.00 HRS	\$ 186,000.00	\$ -	\$ -	\$ 186,000.00	\$ 186,000		
				Sub Total											\$ 186,000	\$ -	\$ -			\$ 186,000	
FOUNDATION PLAN																					
PILE CAPS																					
2	S101	J12/S533		Concrete (5000 Psi)	888	10%	976	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	1795.52 HRS	\$ 183,143.08	\$ 310,171.50	\$ -	\$ 505.21	\$ 493,315		
3	S101	J12/S533		Reinforcement	180069	10%	198,076	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	3378.94 HRS	\$ 344,652.35	\$ 587,097.46	\$ -	\$ 4.70	\$ 931,750		
4	S101	J12/S533		Formwork, Pad footings	3575	10%	3,933	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	382.17 HRS	\$ 38,981.01	\$ -	\$ -	\$ 9.91	\$ 38,981		
5	S101	J12/S533		Excavation	1384	10%	1,522	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	916.80 HRS	\$ 93,513.54	\$ -	\$ -	\$ 61.44	\$ 93,514		
6	S101	J12/S533		Backfill	509	10%	560	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	287.22 HRS	\$ 29,296.16	\$ -	\$ -	\$ 52.31	\$ 29,296		
THICKENED EDGE L=25'-4" W=3'-6" D=2'																					
7	S105	K4/S531		Concrete (5000 Psi)	7	10%	7	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	13.30 HRS	\$ 1,356.49	\$ 2,297.35	\$ -	\$ 505.21	\$ 3,654		
8	S105	K4/S531		(9) #5 Cont. Bar	276	10%	304	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.18 HRS	\$ 528.54	\$ 900.34	\$ -	\$ 4.70	\$ 1,429		
9	S105	K4/S531		#5 @ 12" O.C Dowel	295	10%	325	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	5.54 HRS	\$ 564.64	\$ 961.83	\$ -	\$ 4.70	\$ 1,526		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 692,036	\$ 901,428	\$ -			\$ 1,593,464	
TIE BEAMS																					
10	S101	A1/S523		Concrete (5000 Psi)	116	10%	127	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	233.87 HRS	\$ 23,854.34	\$ 40,399.76	\$ -	\$ 505.21	\$ 64,254		
11	S101	A1/S523		Reinforcement (Tension Ties)	27817	10%	30,599	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	521.98 HRS	\$ 53,241.49	\$ 90,694.12	\$ -	\$ 4.70	\$ 143,936		
12	S101	A1/S523		Reinforcement	5595	10%	6,155	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	105.00 HRS	\$ 10,709.70	\$ 18,243.42	\$ -	\$ 4.70	\$ 28,953		
13	S101	A1/S523		Formwork Beams	1701	10%	1,871	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	181.85 HRS	\$ 18,548.82	\$ -	\$ -	\$ 9.91	\$ 18,549		
14	S101	A1/S523		Excavation	167	10%	183	CY	\$ 51.20	\$ -	\$ -	0.60 HRS	\$ 85	110.36 HRS	\$ 11,257.02	\$ -	\$ -	\$ 61.44	\$ 11,257		
15	S101	A1/S523		Backfill	133	10%	146	CY	\$ 43.59	\$ -	\$ -	0.51 HRS	\$ 85	74.76 HRS	\$ 7,625.63	\$ -	\$ -	\$ 52.31	\$ 7,626		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 125,237	\$ 149,337	\$ -			\$ 274,574	
CONCRETE WALLS																					
16	S101	A12/S533		Concrete (5000 Psi)	19	10%	21	CY	\$ 156.30	\$ 264.71	\$ -	1.84 HRS	\$ 85	37.80 HRS	\$ 3,856.05	\$ 6,530.61	\$ -	\$ 505.21	\$ 10,387		
17	S101	A12/S533		Reinforcement	5076	10%	5,584	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	95.25 HRS	\$ 9,715.52	\$ 16,549.89	\$ -	\$ 4.70	\$ 26,265		
18	S101	A12/S533		Formwork Walls	1009	10%	1,110	SFCA	\$ 8.26	\$ -	\$ -	0.10 HRS	\$ 85	107.88 HRS	\$ 11,004.16	\$ -	\$ -	\$ 9.91	\$ 11,004		
				Please see next tab for detailed calculations																	
				Sub Total											\$ 24,576	\$ 23,080	\$ -			\$ 47,656	
FOUNDATION PLAN																					
SLABS ON GRADE																					
8" SLAB ON GRADE																					
19	S115	Plan	134 CY	8" Thick New Slab W/ #6 @ 12" O.C EW Bars	4930	10%	5,423	SF	\$ 4.16	\$ 7.29	\$ -	0.05 HRS	\$ 85	265.39 HRS	\$ 27,069.58	\$ 47,436.84	\$ -	\$ 13.74	\$ 74,506		
20	S115	Plan		#6 @ 12" O.C EW Bars	17634	10%	19,397	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	330.90 HRS	\$ 33,751.43	\$ 57,493.82	\$ -	\$ 4.70	\$ 91,245		
21	S115	Plan		Vapor Barrier	4930	10%	5,423	SF	\$ 0.67	\$ 0.77	\$ -	0.01 HRS	\$ 85	42.74 HRS	\$ 4,359.76	\$ 5,010.48	\$ -	\$ 1.73	\$ 9,370		
22	S115	Plan		Compacted Fill	4930	10%	5,423	SF	\$ 0.75	\$ -	\$ -	0.01 HRS	\$ 85	47.85 HRS	\$ 4,880.33	\$ -	\$ -	\$ 0.90	\$ 4,880		
23	S115	Plan		Sawcut Control Joint	789	10%	868	LF	\$ 1.40	\$ -	\$ -	0.02 HRS	\$ 85	14.29 HRS	\$ 1,457.59	\$ -	\$ -	\$ 1.68	\$ 1,458		
24	S115	Plan		Expansion Joint	394	10%	434	LF	\$ 1.16	\$ 1.42	\$ -	0.01 HRS	\$ 85	5.92 HRS	\$ 603.86	\$ 739.21	\$ -	\$ 3.10	\$ 1,343		
25	S115	Plan		8" Edge Form	448	10%	493	LF	\$ 6.85	\$ 2.73	\$ -	0.08 HRS	\$ 85	39.71 HRS	\$ 4,050.82	\$ 1,614.41	\$ -	\$ 11.50	\$ 5,665		
12.5" SLAB ON GRADE																					
26	S115	Plan	255 CY	12.5" Concrete Slab at Keel section W/ #6 @ 12" O.C EW T&B Bars	6019	10%	6,621	SF	\$ 5.94	\$ 10.26	\$ -	0.07 HRS	\$ 85	462.66 HRS	\$ 47,191.74	\$ 81,513.00	\$ -	\$ 19.44	\$ 128,705		
27	S115	Plan		#6 @ 12" O.C EW T&B Bars	43060	10%	47,366	LB	\$ 1.45	\$ 2.47	\$ -	0.02 HRS	\$ 85	808.00 HRS	\$ 82,416.36	\$ 140,392.01	\$ -	\$ 4.70	\$ 222,808		
28	S115	Plan		Vapor Barrier	6019	10%	6,621	SF	\$ 0.67	\$ 0.77	\$ -	0.01 HRS	\$ 85	52.19 HRS	\$ 5,322.97	\$ 6,117.45	\$ -	\$ 1.73	\$ 11,440		
29	S115	Plan		Compacted Fill	6019	10%	6,621	SF	\$ 0.75	\$ -	\$ -	0.01 HRS	\$ 85	58.42 HRS	\$ 5,958.55	\$ -	\$ -	\$ 0.90	\$ 5,959		
30	S115	Plan		Sawcut Control Joint	963	10%	1,059	LF	\$ 1.40	\$ -	\$ -	0.02 HRS	\$ 85	17.45 HRS	\$ 1,779.62	\$ -	\$ -	\$ 1.68	\$ 1,780		
31	S115	Plan		Expansion Joint	481	10%	530	LF	\$ 1.16	\$ 1.42	\$ -	0.01 HRS	\$ 85	7.23 HRS	\$ 737.27	\$ 902.52	\$ -	\$ 3.10	\$ 1,640		

HANGER 1														
Dwg No	Detail No	Description	Area	Width	Depth	Counts	Concrete	Formwork	Excavation	Backfill	Description	Rebars	Rebars	Rebars
			SF	FT	FT	EA	CY	SPCA	CY	CY		LB	LB	LB
PAD FOOTINGS														
S101	K4/S531	66" Thick Pile Cap - K4/S531	2561.70		5.50	1	521.8	1782	779	257	#8 @ 6" O.C EW T&B Bars #4 @ 7" O.C Side Bars (2) #8 @ 6" O.C Side Dowels	68397	2564	21660
S101	A8/S522	48" Thick Pile Cap - A8/S522	2356.25		4.00	1	349.1	1668	599	250	#8 @ 8" O.C EW T&B Bars #6 @ 8" O.C EW T&B Bars (4) #4 @ 12" O.C U Bars	46949	25160	6920
S101	A8/S522	14" Thick Concrete Mat - A7/S535	325.00		1.17	1	14.1	125			#6 @ 8" O.C EW T&B Bars #6 @ 8" O.C EW T&B Bars (4) #4 @ 12" O.C U Bars	835	663	6920
TOTAL			5243			3	885	3575	1378	507	Reinforcement	116181	28387	35581
RECAP QUANTITIES FOR PAD FOOTINGS														
Concrete			885				CY							
Reinforcement			180069				LB							
Formwork			3575				SPCA							
Excavation			1378				CY							
Backfill			507				CY							
HANGER 4														
Dwg No	Detail No	Description	Area	Width	Depth	Counts	Concrete	Formwork	Excavation	Backfill	Description	Rebars	Rebars	Rebars
			SF	FT	FT	EA	CY	SPCA	CY	CY		LB	LB	LB
PAD FOOTINGS														
S101	K4/S531	66" Thick Pile Cap - K4/S531	2560.94		5.50	1	521.7	1782	779	257	#8 @ 6" O.C EW T&B Bars #4 @ 7" O.C Side Bars (2) #8 @ 6" O.C Side Dowels	68377	2564	21660
S101	A8/S522	48" Thick Pile Cap - A8/S522	2395.05		4.00	1	354.8	1668	608	253	#8 @ 8" O.C EW T&B Bars #6 @ 8" O.C EW T&B Bars (4) #4 @ 12" O.C U Bars	47722	25574	6920
S101	A8/S522	14" Thick Concrete Mat - A7/S535	307.00		1.17	1	13.3	125			#6 @ 8" O.C EW T&B Bars #6 @ 8" O.C EW T&B Bars (4) #4 @ 12" O.C U Bars	835	663	6920
TOTAL			5263			3	890	3575	1387	510	Reinforcement	116934	28891	35581
RECAP QUANTITIES FOR PAD FOOTINGS														
Concrete			890				CY							
Reinforcement			180069				LB							
Formwork			3575				SPCA							
Excavation			1387				CY							
Backfill			510				CY							
HANGER 5														
Dwg No	Detail No	Description	Area	Width	Depth	Counts	Concrete	Formwork	Excavation	Backfill	Description	Rebars	Rebars	Rebars
			SF	FT	FT	EA	CY	SPCA	CY	CY		LB	LB	LB
PAD FOOTINGS														
S101	K4/S531	66" Thick Pile Cap - K4/S531	2559.99		5.50	1	521.4	1782	778	257	#8 @ 6" O.C EW T&B Bars #4 @ 7" O.C Side Bars (2) #8 @ 6" O.C Side Dowels	68341	2564	21660
S101	A8/S522	48" Thick Pile Cap - A8/S522	2383.50		4.00	1	353.1	1668	605	252	#8 @ 8" O.C EW T&B Bars #6 @ 8" O.C EW T&B Bars (4) #4 @ 12" O.C U Bars	47492	25451	6920
S101	A8/S522	14" Thick Concrete Mat - A7/S535	304.00		1.17	1	13.2	125			#6 @ 8" O.C Long Bars #4 @ 12" O.C Trans. Bars	835	663	6920
TOTAL			5247			3	888	3575	1384	509	Reinforcement	116668	28678	35581
RECAP QUANTITIES FOR PAD FOOTINGS														
Concrete			888				CY							
Reinforcement			180069				LB							
Formwork			3575				SPCA							
Excavation			1384				CY							
Backfill			509				CY							

Dwg No	Detail No	Description	Length	Width	Depth	Concrete	Formwork	Excavation	Backfill	Description	Cont. Tension Ties
			FT	FT	FT	CY	SFCA	CY	CY		LB
WALL FOOTINGS											
S105	A1/S523	44" x 14" Grade Beam - A1/S523	727.17	3.67	1.17	116	1702	167	133	6 #11 Cont. Bars (Tension Ties) #4 @ 12" O.C Ties	27817
TOTAL			727			116	1702	167	133	Reinforcement	27817

RECAP QUANTITIES FOR WALL FOOTINGS

Concrete	116	CY
Reinforcement (Tention Ties)	27817	LB
Reinforcement	5595	LB
Formwork	1702	SFCA
Excavation	167	CY
Backfill	133	CY

HANGER 4

Dwg No	Detail No	Description	Length	Width	Depth	Concrete	Formwork	Excavation	Backfill	Description	Cont. Tension Ties
			FT	FT	FT	CY	SFCA	CY	CY		LB
WALL FOOTINGS											
S105	A1/S523	44" x 14" Grade Beam - A1/S523	726.92	3.67	1.17	116	1701	167	133	6 #11 Cont. Bars (Tension Ties) #4 @ 12" O.C Ties	27807
TOTAL			727			116	1701	167	133	Reinforcement	27807

RECAP QUANTITIES FOR WALL FOOTINGS

Concrete	116	CY
Reinforcement (Tention Ties)	27817	LB
Reinforcement	5595	LB
Formwork	1701	SFCA
Excavation	167	CY
Backfill	133	CY

HANGER 5

Dwg No	Detail No	Description	Length	Width	Depth	Concrete	Formwork	Excavation	Backfill	Description	Cont. Tension Ties
			FT	FT	FT	CY	SFCA	CY	CY		LB
WALL FOOTINGS											
S105	A1/S523	44" x 14" Grade Beam - A1/S523	727.02	3.67	1.17	116	1701	167	133	6 #11 Cont. Bars (Tension Ties) #4 @ 12" O.C Ties	27811
TOTAL			727			116	1701	167	133	Reinforcement	27811

RECAP QUANTITIES FOR WALL FOOTINGS

Concrete	116	CY
Reinforcement (Tention Ties)	27817	LB
Reinforcement	5595	LB
Formwork	1701	SFCA
Excavation	167	CY
Backfill	133	CY

