

PROJECT ADDRESS		GAINES PARK COMMUNITY CENTER AND TENNIS CENTER														
Date of submission		1501 N. Australian Ave., West Palm Beach, FL 33401														
Date of plans		1/22/2024														
Date of plans		4/10/2023														
BASE BID		\$ - STRUCTURAL STEEL - COMMUNITY CENTER														
ADD ALT #1		\$ - STRUCTURAL STEEL - COMMUNITY CENTER - ADD ALT #1														
BASE BID		\$ - STRUCTURAL STEEL - TENNIS CENTER														

Pricing cells

Confirm pricing

Confirm inclusion in scope

Email

support@aconengineering.com

PH #

Website

http://aconengineering.com/

ACON

ENGINEERING

O&P	
0.00%	

SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY	WASTE	QTY. W/ WASTE	UNIT	LABOR/EQUIPMENT COST	MATERIAL COST	SUBCONTRACTOR COST	TOTAL LABOR	TOTAL MATERIAL	TOTAL SUB	TOTAL UNIT COST	TOTAL COST	SUBTOTAL	
TOTAL																\$ -	\$ -	
SALES & USE TAX (MATERIAL)																7.000%	\$ -	
BASEBID																\$ -		
05 00 00 METALS - COMMUNITY CENTER - ADD ALT #1																		
				STRUCTURALFRAMING														
				BEAMS														
29	S-1.2.0			L4x4x1/4 - L-1 = 67 LF	439	10%	483	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
30	S-1.2.0			L6x4x5/16 - L-2 = 93 LF	958	10%	1,054	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
31	S-1.2.0			L4x4x1/4 - L-3 = 67 LF	443	10%	487	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				JOISTS														
32	S-1.2.0			20K4 = 341 LF	2,455	10%	2,701	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
33	S-1.2.0			20KCS2 = 124 LF	1,178	10%	1,296	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				METAL DECK														
34	S-1.2.0			1.5B20 GA Metal deck	2,363	10%	2,599	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				MISC STEEL														
35				Misc steel connections and plates (5%)	274	10%	301	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				Alternate # 1 Sub-Total								\$ -	\$ -	\$ -			\$ -	
TOTAL																\$ -	\$ -	
SALES & USE TAX (MATERIAL)																7.000%	\$ -	
ALTERNATE #1																\$ -		
05 00 00 METALS - TENNIS CENTER																		
		Steel note D at S-1.3.0	STRUCTURALSTEEL															
			Note: All steel to have shop coat of rust inhibitive paint															
				TENNIS CENTER STRUCTURALFRAMING														
				BEAMS														
36	S2.1.0	1,3&8/S2.4.0		L4x4x1/4 - L-1 = 65 LF	429	10%	472	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
37	S2.1.0	6,7&9/S2.4.0		L6x4x5/16 - L-2 = 79 LF	814	10%	895	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
38	S2.1.0			HSS14x6x1/4 = 77 LF	2,494	10%	2,744	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
39	S2.1.0			W12x14 = 47 LF	648	10%	713	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
40	S2.1.0			W16x26 = 156 LF	4,038	10%	4,442	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				JOISTS														
41	S2.1.0			Roof joist - 10K1 = 73 LF	364	10%	400	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
42	S2.1.0			Roof joist - 18K4 = 86 LF	619	10%	681	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
43	S2.1.0			Roof joist - 18KCS3 = 229 LF	2,521	10%	2,773	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				COLUMNS														
44	S2.1.0			HSS6x6x1/2 = 27 LF	960	10%	1,056	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				DECKING														
45	S2.1.0			1.5B 20GA Metal deck	2,172	10%	2,389	SF	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				MISC STEEL														
46				Misc steel connections and plates (5%)	644	10%	709	LB	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
				Tennis Center Structural Steel Sub-Total								\$ -	\$ -	\$ -			\$ -	

